

Executant: 03 S.C.LDP REISER SA.BARLAD

Obiectiv: 991 ANALIZE PRET II 2019

Obiect: 10 MONTAT BORDURI MICI - 2019

Categorie: 01 Montat borduri (50x10x15cm)

Formularul C4

LISTA CUPRINZAND CANTITATILE DE LUCRARI

Nr.	Capitolul de lucrari	U/M	Cantitatea	Pretul unitar	Total
Crt.	Simbol				
	Denumire resursa				
	Observatii				
1	CZ0104C1 82	M CUB	0.02000	351.91422	7.04
	PREPARARE BETON B100 CU BALAST,GRANULATIA<31MM CU CIMENT F25,MANUAL		\$		
2	DE11A1 82	M	1.00000	24.52654	24.53
	BORD MICI PREF BETON 10 X 15 CM PT INCADR TROTUARESPATII VERZI ALEI ASEZATE FUND BETON 10 X 20 CM				
3	TSA02XB 93	M CUB	0.04000	66.81019	2.67
	SAPATURA MANUALA DE PAMINT IN SPATII LIMITATE,AVIND SUB 1,00 M LAT.TEREN MIJLOCIU				
4	TRA01A10 82	TONE	0.08000	7.49840	0.60
	TRANSPORTUL RUTIER AL MATERIALELOR,SEMIFABRICATELOR CU AUTOBASCULANTA PE DIST.= 10 KM.		\$		
5	TRB01A12 82	TONE	0.08000	28.45717	2.28
	TRANSPORTUL MATERIALELOR CU ROABA PE PNEURI INC ASEZARE DESC ASEZARE GRUPA 1-3 DISTANTA 20M		\$		
Total general deviz pe categoria de lucrari:					37.11

Formular F3

Obiectiv: 991 ANALIZE PRET II 2019

LISTA cu cantitatile de lucrari pe categorii de lucrari

Obiect: 10 MONTAT BORDURI MICI - 2019

Categorie: 01 Montat borduri (50x10x15cm)

[ron]

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	
1	CZ0104C1 82	M CUB	0.02000	195.48940	3.91
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
				109.20000	2.18
	PREPARARE BETON B100 CU BALAST,GRANULATIA<31MM CU CIMENT F25,MANUAL			0.00000	0.00
	\$			0.00000	0.00
				304.68940	6.09
2	DE11A1 82	M	1.00000	10.76196	10.76
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
				9.46701	9.47
	BORD MICI PREF BETON 10 X 15 CM PT INCADR TROTUARESPATII VERZI ALEI ASEZATE			1.00000	1.00
	FUND BETON 10 X 20 CM			0.00000	0.00
				21.22897	21.23
3	TSA02XB 93	M CUB	0.04000	0.00000	0.00
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
				57.72000	2.31
	SAPATURA MANUALA DE PAMINT IN SPATII LIMITATE,AVIND SUB 1,00 M LAT.TEREN MIJLOCIU			0.00000	0.00
				0.00000	0.00
				57.72000	2.31
4	TRA01A10 82	TONE	0.08000	0.00000	0.00
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
				0.00000	0.00
	TRANSPORTUL RUTIER AL MATERIALELOR,SEMIFABRICATELOR CU AUTOBASCULANTA PE DIST.= 10 KM.			0.00000	0.00
	\$			6.50000	0.52
				6.50000	0.52
5	TRB01A12 82	TONE	0.08000	0.00000	0.00
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
				24.58529	1.97
	TRANSPORTUL MATERIALELOR CU ROABA PE PNEURI INC ASEZARE DESC ASEZARE GRUPE 1-3 DISTANTA 20M			0.00000	0.00
	\$			0.00000	0.00
				24.58529	1.97
Total A:					14.67
					15.93
					1.00
					0.52
					32.12

Executant: 03 -S.C.LDP REISER SA.BARLAD
Obiectiv: 991 -ANALIZE PRET II 2019
Obiect: 10 -MONTAT BORDURI MICI - 2019
Categorie: 01 -Montat borduri (50x10x15cm)

Recapitulatie

	Material M	Manopera m	Utilaj U	Transport t	Total T
Cheltuieli directe	14.67	15.93	1.00	0.52	32.12
din care utilaje			0.00		
- Vut termice			0.00		
- Vut electrice			1.00		
- Vut altele					
Alte cheltuieli directe		0.05			0.05
CAM					
	Mo	mo	Uo	to	To
TOTAL CHELT. DIRECTE	14.67	15.98	1.00	0.52	32.17
Cheltuieli indirecte	Io = ##### x Io				3.86
Profit	Po = 3.000% x (To+Io)				1.08
TOTAL GENERAL categorie	Vo = To+Io+Po				37.11