

Executant: 03 S.C.LDP REISER SA.BARLAD

Obiectiv: 991 ANALIZE PRET II 2019

Obiect: 02 REP.STRAZI- PLOMBARI M.A./2019

Categorie: 01 Plombari cu mixt. asfaltice/mp

Formularul C4

LISTA CUPRINZAND CANTITATILE DE LUCRARI

Nr.	Capitolul de lucrari	U/M	Cantitatea	Pretul unitar	Total
Crt.	Simbol				
	Denumire resursa				
	Observatii				
1	DZ31B1 82	TONE	0.10000	448.84065	44.88
	PREP BAPC 8, LA CALD CU BITUM PT REPAR SUPRAF DEGRAD SI PLOMB GROU IN INST TIP IMA10				
2	DI02D1 82	MP	1.00000	60.24063	60.24
	REP SUPR DEGR INCL PLOMB GROPI LA IMBR BIT CU MORT. ASF PREP LA CALD CU DECAP MANUALA(4-5CM GROSIME				
3	DI19C1 82	ORE	0.06000	78.44480	4.71
	UTILAJE MIJ TRANSP REP INTR DR AUTOCAMION AUTOBASCTRANSF TEHNOLOGIC BENA BASCULABILA DE 5,5 T				
4	DF27A1 82	ORE	0.10000	36.11361	3.61
	PILOTI PT DIRIJ CIRC RUT IN SCOP ASIG FLUENT TRAF PE SECT DR CU RESTR DE CIRC PTR LUCR .REPARATII				
5	TRA05A05 82	TONE	0.10000	5.76800	0.58
	TRANSPORT RUTIER AL MATERIALELOR REZULTATE DIN DECAPAREA SUPRAFETEI ,CU AUTOVEHIC.PE DIST.DE 5 KM.\$				
6	DI19F1 82	ORE	0.06000	57.68000	3.46
	MIJLOACE DE TRANSP,PT.REP.SI INTRET.DRUMURILOR, AUTO. TIP DACIA PAPUC PT.TRANSPOT SCULE SI MUNCITORI				
Total general deviz pe categoria de lucrari:					117.48

Formular F3

Obiectiv: 991 ANALIZE PRET II 2019

LISTA

cu cantitatile de lucrari pe categorii de lucrari

Obiect: 02 REP.STRAZI- PLOMBARI M.A./2019

Categorie: 01 Plombari cu mixt. asfaltice/mp

[ron]

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	
1	DZ31B1 82	TONE	0.10000	275.29000	27.53
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	49.92000
					4.99
	PREP BAPC 8, LA CALD CU BITUM PT REPAR SUPRAF DEGRAD SI PLOMB GROU IN INST TIP IMA10			63.70000	6.37
				0.00000	0.00
				388.91000	38.89
2	DI02D1 82	MP	1.00000	2.22300	2.22
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	40.56000
					40.56
	REP SUPR DEGR INCL PLOMB GROPI LA IMBR BIT CU MORT. ASF PREP LA CALD CU DECAP MANUALA(4-5CM GROSIME			9.30000	9.30
				0.00000	0.00
				52.08300	52.08
3	DI19C1 82	ORE	0.06000	0.00000	0.00
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	0.00000
					0.00
	UTILAJE MIJ TRANSP REP INTR DR AUTOCAMION AUTOBASCTRANSP TEHNOLOGIC BENA BASCULABILA DE 5,5 T			68.00000	4.08
				0.00000	0.00
				68.00000	4.08
4	DF27A1 82	ORE	0.10000	0.00000	0.00
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	31.20000
					3.12
	PILOTI PT DIRIJ CIRC RUT IN SCOP ASIG FLUENT TRAF PE SECT DR CU RESTR DE CIRC PTR LUCR .REPARATII			0.00000	0.00
				0.00000	0.00
				31.20000	3.12
5	TRA05A05 82	TONE	0.10000	0.00000	0.00
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	0.00000
					0.00
	TRANSPORT RUTIER AL MATERIALELOR REZULTATE DIN DECAPAREA SUPRAFETEI ,CU AUTOVEHIC.PE DIST.DE 5 KM.Ş			0.00000	0.00
				5.00000	0.50
				5.00000	0.50
6	DI19F1 82	ORE	0.06000	0.00000	0.00
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	0.00000
					0.00
	MIJLOACE DE TRANSP,PT.REP.SI INTRET.DRUMURILOR, AUTO. TIP DACIA PAPUC PT.TRANSPOT SCULE SI MUNCITORI			50.00000	3.00
				0.00000	0.00
				50.00000	3.00
Total A:					29.75
					48.67
					22.75
					0.50
					101.67

Executant: 03 -S.C.LDP REISER SA.BARLAD
Obiectiv: 991 -ANALIZE PRET II 2019
Obiect: 02 -REP.STRAZI- PLOMBARI M.A./2019
Categorie: 01 -Plombari cu mixt. asfaltice/mp

Recapitulatie

	Material M	Manopera m	Utilaj U	Transport t	Total T
Cheltuieli directe	29.75	48.67	22.75	0.50	101.67
din care utilaje					
- Vut termice			8.48		
- Vut electrice			0.38		
- Vut altele			13.89		
Alte cheltuieli directe		0.16			0.16
CAM					
	0.337%				
TOTAL CHELT. DIRECTE	Mo 29.75	mo 48.84	Uo 22.75	to 0.50	To 101.84
Cheltuieli indirecte					12.22
Profit					3.42
TOTAL GENERAL categorie					Vo = To+Io+Po 117.48

Io = ##### x Io
 Po = 3.000% x (To+Io)