

Executant: 03 S.C.LDP REISER SA.BARLAD

Obiectiv: 991 ANALIZE PRET II 2019

Obiect: 11 REPARATII TROTUARE - 2019

Categorie: 03 Reamenajare trot. cu asfalt.

Formularul C4

LISTA CUPRINZAND CANTITATILE DE LUCRARI

Nr.	Capitolul de lucrari	U/M	Cantitatea	Pretul unitar	Total
Crt.	Simbol				
	Denumire resursa				
	Observatii				
1	DZ31B1 82	TONE	0.10000	448.84065	44.88
	PREP MORTAR ASF LA CALD CU ADAOS DE CRIB SI BIT PTREPAR SUPRAF DEGRAD SI PLOMB GROU IN INST TIP ANG5				
2	DB16D1 82	MP	1.00000	37.24148	37.24
	IMBRAC BET ASF CU AGREGAT MARUNT EXEC LA CALD IN GROS DE 4,0CM ASTERN MANUALA				
3	DI19C1 82	ORE	0.06000	78.44480	4.71
	UTILAJE MIJ TRANSP REP INTR DR AUTOCAMION AUTOBASCTRANSF TEHNOLOGIC BENA BASCULABILA DE 5,5 T				
4	DI19F1 82	ORE	0.06000	57.68000	3.46
	UTILAJE MIJ TRANSP REP INTR DE DRUMURI , AUTOUTILITARA PT.TRANSPORT MUNCITORI,UNELTE ETC.				
Total general deviz pe categoria de lucrari:					90.29

Formular F3

Obiectiv: 991 ANALIZE PRET II 2019

LISTA cu cantitatile de lucrari pe categorii de lucrari

Obiect: 11 REPARATII TROTUARE - 2019

Categorie: 03 Reamenajare trot. cu asfalt.

[ron]

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	
1	DZ31B1 82	TONE	0.10000	275.29000	27.53
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
				49.92000	4.99
	PREP MORTAR ASF LA CALD CU ADAOS DE CRIB SI BIT PTPREPAR SUPRAF DEGRAD SI			63.70000	6.37
	PLOMB GROU IN INST TIP ANGŞ			0.00000	0.00
				388.91000	38.89
2	DB16D1 82	MP	1.00000	2.00100	2.00
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
				29.32800	29.33
	IMBRAC BET ASF CU AGREGAT MARUNT EXEC LA CALD IN GROS DE 4,0CM ASTERN			0.85500	0.86
	MANUALA			0.00000	0.00
				32.18400	32.18
3	DI19C1 82	ORE	0.06000	0.00000	0.00
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
				0.00000	0.00
	UTILAJE MIJ TRANSP REP INTR DR AUTOCAMION AUTOBASCTRANSP TEHNOLOGIC BENA			68.00000	4.08
	BASCULABILA DE 5,5 T			0.00000	0.00
				68.00000	4.08
4	DI19F1 82	ORE	0.06000	0.00000	0.00
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
				0.00000	0.00
	UTILAJE MIJ TRANSP REP INTR DE DRUMURI , AUTOUTILITARA PT.TRANSPORT			50.00000	3.00
	MUNCITORI,UNELTE ETC.			0.00000	0.00
				50.00000	3.00
Total A:					29.53
					34.32
					14.31
					0.00
					78.16

Executant: 03 -S.C.LDP REISER SA.BARLAD
Obiectiv: 991 -ANALIZE PRET II 2019
Obiect: 11 - REPARATII TROTUARE - 2019
Categorie: 03 -Reamenajare trot. cu asfalt.

Recapitulatie

	Material M	Manopera m	Utilaj U	Transport t	Total T
Cheletuieii directe	29.53	34.32	14.31	0.00	78.16
din care utilaje					
- Vut termice			9.34		
- Vut electrice			0.38		
- Vut altele			4.59		
Alte cheletuieii directe		0.12			0.12
CAM					
TOTAL CHELT. DIRECTE	29.53	34.44	14.31	0.00	78.27
Cheletuieii indirecte					9.39
Profit					2.63
TOTAL GENERAL categorie	Vo = TotIo+Po				90.29

Io = ##### x Io
 Po = 3.000% x (To+Io)