

Executant: 03 S.C.LDP REISER SA.BARLAD

Obiectiv: 991 ANALIZE PRET II 2019

Obiect: 03 COVOARE ASFALTICE - 2019

Categorie: 02 IMBRACAMINTE BAPC8 / 4 cm

Formularul C4**LISTA CUPRINZAND CANTITATILE DE LUCRARI**

Nr.	Capitolul de lucrari	U/M	Cantitatea	Pretul unitar	Total
Crt.	Simbol				
	Denumire resursa				
	Observatii				
1	DG05A1 82	MP	0.10000	26.78409	2.68
	DECAP IMBR CU STRAT PINA LA 3CM GROS FORMATE DIN COVOARE ASFALTICE PERMANENTE,BETOANE ASFALTICE				
2	DB01C1 82	MP	1.00000	5.38042	5.38
	CURATIREA PT APLIC IMBRAC SAU TRATAM BITUM A STRATSUPPORT DIN SUPRA BIT DIN BET CIM SAU PAV BITUMAT \$				
3	DB02C1 82	SUTE MP	0.01000	457.46088	4.57
	AMORS SUPRAF STRAT BAZA SAU IMBRAC EXIST IN VEDER APLIC STRAT UZ MIX ASF CU BITUM TAIAT				
4	DZ14A1 82	TONE	0.09600	448.84065	43.09
	PREP BETON ASFALTIC FIN BOGAT IN CRIBLURA EXECUTATLA CALD CU BITUM, BAPC8, IN INSTALATII TIP IMA 10				
5	DB16D1 82	MP	1.00000	21.02812	21.03
	IMBRAC BET ASF CU AGREGAT MARUNT EXEC LA CALD IN GROS DE 4,0CM ASTERN MANUALA				
6	DI19C1 82	ORE	0.06000	78.44480	4.71
	UTILAJE MIJ TRANSP REP INTR DR AUTOCAMION AUTOBASCTRANSF TEHNOLOGIC BENA BASCULABILA DE 8,0T				
7	DF27A1 82	ORE	0.10000	36.11361	3.61
	PILOTIPT DIRIJ CIRC RUT IN SCOP ASIG FLUENT TRAF PE SECT DR CU RESTR DE CIRC PTR LUCR CONST,REP				
8	DI19F1 82	ORE	0.06000	57.68000	3.46
	UTILAJE MIJ TRANSP REP INTR DRUMURI, TIP AUTOUTILITARA PT. TRANSPORT MUNCITORI,UNELTE,SCULE,ETC				
Total general deviz pe categoria de lucrari:					88.53

Formular F3

Obiectiv: 991 ANALIZE PRET II 2019

LISTA cu cantitatile de lucrari pe categorii de lucrari

Obiect: 03 COVOARE ASFALTICE - 2019

Categorie: 02 IMBRACAMINTE BAPC8 / 4 cm

[ron]

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	
1	DG05A1 82	MP	0.10000	0.00000	0.00
				17.16000	1.72
				6.00000	0.60
	DECAP IMBR CU STRAT PINA LA 3CM GROS FORMATE DIN COVOARE ASFALTICE PERMANENTE,BETOANE ASFALTICE			0.00000	0.00
				23.16000	2.32
2	DB01C1 82	MP	1.00000	0.01296	0.01
				3.12000	3.12
				1.52055	1.52
	CURATIREA PT APLIC IMBRAC SAU TRATAM BITUM A STRATSUPPORT DIN SUPRA BIT DIN BET CIM SAU PAV BITUMAT \$			0.00000	0.00
				4.65351	4.65
3	DB02C1 82	SUTE MP	0.01000	252.23460	2.52
				140.42586	1.40
				3.41700	0.03
	AMORS SUPRAF STRAT BAZA SAU IMBRAC EXIST IN VEDER APLIC STRAT UZ MIX ASF CU BITUM TAIAT			0.00000	0.00
				396.07746	3.96
4	DZ14A1 82	TONE	0.09600	275.29000	26.43
				49.92000	4.79
				63.70000	6.12
	PREP BETON ASFALTIC FIN BOGAT IN CRIBLURA EXECUTATLA CALD CU BITUM, BAPC8, IN INSTALATII TIP IMA 10			0.00000	0.00
				388.91000	37.34
5	DB16D1 82	MP	1.00000	0.02436	0.02
				16.34880	16.35
				1.80000	1.80
	IMBRAC BET ASF CU AGREGAT MARUNT EXEC LA CALD IN GROS DE 4,0CM ASTERN MANUALA			0.00000	0.00
				18.17316	18.17
6	DI19C1 82	ORE	0.06000	0.00000	0.00
				0.00000	0.00
				68.00000	4.08
	UTILAJE MIJ TRANSP INTR DR AUTOCAMION AUTOBASCTRANSP TEHNOLOGIC BENA BASCULABILA DE 8,0 T			0.00000	0.00
				68.00000	4.08
7	DF27A1 82	ORE	0.10000	0.00000	0.00
				31.20000	3.12
				0.00000	0.00
	PILOTIPT DIRIJ CIRC RUT IN SCOP ASIG FLUENT TRAF PE SECT DR CU RESTR DE CIRC PTR LUCR CONST,REP			0.00000	0.00
				31.20000	3.12

Executant: 03 -S.C.LDP REISER SA.BARLAD
 Obiectiv: 991 -ANALIZE PRET II 2019
 Obiect: 03 -COVOARE ASFALTICE - 2019
 Categorie: 02 -IMBRACAMINTE BAPC8 / 4 cm

Recapitulatie

	Material M	Manopera m	Utilaj U	Transport t	Total T
Cheltuieli directe	28.99	30.50	17.15	0.00	76.64
din care utilaje			10.24		
- Vut termice			0.36		
- Vut electrice			6.54		
- Vut altele					
Alte cheltuieli directe		0.10			0.10
CAM					
	0.337%				
TOTAL CHELT. DIRECTE	28.99	30.60	17.15	0.00	76.74
Cheltuieli indirecte					9.21
Profit					2.58
TOTAL GENERAL categorie					88.53

Io = ##### x To

Po = 3.000% x (To+Io)

Vo = To+Io+Po